




Take a dipp™ sooner with a Drop-In Plunge Pool




Small DIPP'R

WIDTH	HEIGHT	WEIGHT	WATER HEIGHT	CAPACITY
2.5m	1.43m	5.2t	1.2m approx	5,200ltr



Medium DIPP'R

WIDTH	HEIGHT	WEIGHT	WATER HEIGHT	CAPACITY
3.5m	1.43m	7.2t	1.2m approx	10,200ltr



Large DIPP'R

WIDTH	HEIGHT	WEIGHT	WATER HEIGHT	CAPACITY
3.5m	1.63m	9.0t	1.4m approx	12,000ltr



X Large DIPP'R

WIDTH	HEIGHT	WEIGHT	WATER HEIGHT	CAPACITY
3.5m	1.83m	9.2t	1.6m approx	14,200ltr



DIPP'S

WIDTH	LENGTH	HEIGHT	WEIGHT	WATER HEIGHT	CAPACITY
2.48m	2.48m	1.63m	7.2t	1.4m approx	7,000ltr



DIPP42

WIDTH	LENGTH	HEIGHT	WEIGHT	WATER HEIGHT	CAPACITY
2.48m	4.8m	1.63m	10.0t	1.4m approx	13,700ltr



DIPP63

WIDTH	LENGTH	HEIGHT	WEIGHT	WATER HEIGHT	CAPACITY
3m	6m	1.6m	12.7t	1.45m approx	24,000ltr

PLUNGE POOL INCLUSIONS

- Fully reinforced 40Mpa concrete pool shell
- Solid concrete seat and top step (DIPP63 has concrete seat)
- Fitting of 2 x jet eyeballs & skimmer box
- Waterproofing of shell with Mapelastc Smart
- Tiling of pool internally with ceramic mosaic tiles and granite/travertine/limestone coping tiles
- Multi-coloured LED Light and transformer
- Form 15 engineering certificate and drawings

INSTALLATION INCLUSIONS

- QBCC Insurance
- Delivery to most areas
- Council fees by private certifier
- Supply and install gravel screed base for pool
- Installation of pool to manufacturer's specifications
- Temporary pool fence 3 weeks hire
- Filtration: Maytronics cartridge filtration package
- Installation of pool equipment including all pipe and fittings
- Excavation
- Includes lift into place if access permits from delivery truck (except DIPP63 – crane is required)
- Full on site pool startup, chemical balance and handover

OPTIONAL EXTRAS

- ASK ABOUT PRICES
- ▲ Mineral salts
 - ▲ Inverter heat pumps
 - ▲ Additional seat
 - ▲ Upgrade packages on equipment
 - ▲ External tiling
 - ▲ External paint
 - ▲ Solar thermal blankets
 - ▲ Pool robot cleaners



Entity Queensland Plunge Pools ABN 41 636 618 230 QBCC licence number # 15263480

NOT INCLUDED

- ✗ All electrical work
- ✗ Permanent fence
- ✗ Removal of excavated material
- ✗ Crane (if required)
- ✗ Concrete anti-flotation collar

01/09/2023

